



D.V. Electromatic (P) Ltd.



AN ISO 9001:2008 CERTIFIED CO.

REF NO: **DVEPL/20-21/6591/R0**

Date – 20-July-2024

TO,
S.G.ENGINEERING CO
JODHPUR

Kind Attn.: YS.G.ENGINEERING CO
Mobile No.: 9828026311
Email ID: sgengineeringcompany@gmail.com

Sub: **QUOTATION FOR CWE (AF) BKN_SOG- _2024-25 2024_MES_662557_1**

Dear Sir,

We acknowledge with thanks the receipt of your valued enquiry regarding above mentioned subject. We are pleased to furnish our most competitive offer for your favorable consideration as under.

ANNEXURE - I: FABRICATION DETAILS & TECHNICAL SPECIFICATIONS

ANNEXURE - II: BILL OF MATERIAL

ANNEXURE- III: PRICE SCHEDULE

ANNEXURE- IV: TERMS AND CONDITIONS

We hope the detailed BOQ & Tech Specs here under is as per your requirement.

Should you need any further clarification(s) please feel free to contact us. We look forward for an opportunity to serve you.

Thanking you,

Yours faithfully,

For **D.V. ELECTROMATIC PVT. LTD.**

Authorized Signatory

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



ANNEXURE – I

TECHNICAL SPECIFICATIONS

- 1. Material of Sheet:** CRCA sheet
- 2. Sheet thickness:** AS PER TENDER thickness for All Panels.
- 3. Material treatment:** Thorough chemical treatment with 7 tank process method for degreasing, derusting and phosphating powder coating shall not be less than 40 microns.
- SIEMENS GREY (RAL-7032) shade powder coating paint will be applied.
- 4. Bus bar:** The bus bars will be insulated with PVC heat shrinkable sleeves and supported SMC/DMC at Suitable intervals so as to withstand dynamic stresses developed in the event of short circuit of 50ka (RMS) and will withstand following standard tests:-
- (a) Continuity tests
(b) No load operation test
(c) H.T Test (2kV) for one minute.
(d) Insulation resistance test.
- 6. Fault Level:** 35 KA
- 7. Bus Bar Size:** As per BOQ
- 8. Current Density:** 0.8A/Sq. mm. Current Density.
- 9. Bus bar insulation** Heat Shrinkable Sleeves

MANUFACTURERS OF LT CONTROL PANELS

**ANNEXURE – II****BILL OF MATERIALS**

1	SR NO 49		BOARD QTY		
A	INCOMER MCCB 315A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	315A 4P 36kA MCCB (with Spreaders), TM Release (Adj Thermal & Adj Magnetic), Type : TAB3	HPL	TAB630NX315AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 315A TAB3 MCCB	HPL	TAB3315ST4P	1	1
3	ROHM 4P compact Door mounted for TAB3 MCCB	HPL	RHCT3AFDPM	1	1
4	Auxiliary Switch, Contacts: 1 C/O for TAB3 MCCB	HPL	TAB3AUX1CO	1	1
5	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
6	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	1
7	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Multifunction Meter (LED display), 3Ph, Parameters: V, A, F, PF, kW, kVA, Old energy, On hours, site selectable kWh/ kVAh, CL: 1, Aux Sup: 90-300V AC/DC, Size: 96X96	L&T	WL4400100000	1	1
2	Ammeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1310100000	1	1
3	Voltmeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1320100000	1	1
4	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
5	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
6	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
7	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	3	3
8	300/5A 10VA Acc. Cl: 1, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 60mm	NIPPEN	NA	3	3
9	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
10	2A 1P 10kA C-Curve Techno MCB	HPL	NTSPC2	3	3
C	OUTGOING MCCB 100A	MAKE	1	FEEDER QTY	3
1	100A 4P 25kA MCCB (with Spreaders), TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160CY100AC4P	1	3
2	ROHM compact Door mounted for TAB1 MCCB	HPL	RHCT1ACPDM	1	3
3	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	3
4	Auxiliary Switch, Contacts: 1 C/O for TAB1 MCCB	HPL	TAB160AX1C	1	3
5	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	3
6	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	3
7	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	1	3
D	OUTGOING CHILLED WATER PUMP FASD	MAKE	1	FEEDER QTY	2
1	40A 3P 25kA MCCB, TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160CY040AC3P	1	2
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	2
3	ROHM compact Door mounted for TAB1 MCCB	HPL	RHCT1ACPDM	1	2
4	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	2
5	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	2
6	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	1	2
7	Auxiliary Switch, Contacts: 1 C/O for TAB1 MCCB	HPL	TAB160AX1C	1	2
8	AC3: 12A AC1: 25A 3P Power Contactor, Coil Voltage: 240V AC, Aux. contact: 1NO+1NC, Type: SDE-12	HPL	SDE1211A5	3	6

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



9	7.0-10A Thermal Overload Relay, Aux. Contact: 1NO + 1NC, Contactor Type: SDE Contactor, Type: SDER25	HPL	SDER25/10.0	1	2
10	Star Delta Timer, Time Setting: 3sec - 120sec, Voltage: 240V AC - 415V AC, Contact: 1CO (Star) + 1CO (Delta)	GIC	14SDT1S	1	2
11	SPP + Selectable Under Voltage+Selectable Over Voltage Relay ON Delay 0 - 15Sec,Phase 10% fixed Asymmetry, Voltage: 240 VAC,2 C/O, 3Ph/1Ph 4W, Type: SM500	GIC	MG73BH	1	2
12	1NO Contact Block	ESBEE	EC1C	1	2
13	1NC Contact Block	ESBEE	EC2C	1	2
14	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	2
15	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	2
16	Amber Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLA240A	1	2
17	6A 1P 2Way Local - Remote/ Auto-Manual Switch with Center OFF, 60 Deg. Operation	SALZER	61025SAB13	1	2
E	OUTGOING CONDENSER WATER PUMP FASD	MAKE	1	FEEDER QTY	2
1	40A 3P 25kA MCCB, TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160CY040AC3P	1	2
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	2
3	ROHM compact Door mounted for TAB1 MCCB	HPL	RHCT1ACPDM	1	2
4	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	2
5	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	2
6	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	1	2
7	Auxiliary Switch, Contacts: 1 C/O for TAB1 MCCB	HPL	TAB160AX1C	1	2
8	AC3: 12A AC1: 25A 3P Power Contactor, Coil Voltage: 240V AC, Aux. contact: 1NO+1NC, Type: SDE-12	HPL	SDE1211A5	3	6
9	7.0-10A Thermal Overload Relay, Aux. Contact: 1NO + 1NC, Contactor Type: SDE Contactor, Type: SDER25	HPL	SDER25/10.0	1	2
10	Star Delta Timer, Time Setting: 3sec - 120sec, Voltage: 240V AC - 415V AC, Contact: 1CO (Star) + 1CO (Delta)	GIC	14SDT1S	1	2
11	SPP + Selectable Under Voltage+Selectable Over Voltage Relay ON Delay 0 - 15Sec,Phase 10% fixed Asymmetry, Voltage: 240 VAC,2 C/O, 3Ph/1Ph 4W, Type: SM500	GIC	MG73BH	1	2
12	1NO Contact Block	ESBEE	EC1C	1	2
13	1NC Contact Block	ESBEE	EC2C	1	2
14	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	2
15	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	2
16	Amber Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLA240A	1	2
17	6A 1P 2Way Local - Remote/ Auto-Manual Switch with Center OFF, 60 Deg. Operation	SALZER	61025SAB13	1	2
F	OUTGOING COOLING TOWER PUMP FASD	MAKE	1	FEEDER QTY	1
1	40A 3P 25kA MCCB, TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160CY040AC3P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
3	ROHM compact Door mounted for TAB1 MCCB	HPL	RHCT1ACPDM	1	1
4	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
5	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	1
6	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	1	1
7	Auxiliary Switch, Contacts: 1 C/O for TAB1 MCCB	HPL	TAB160AX1C	1	1
8	AC3: 18A AC1: 32A 3P Power Contactor, Coil Voltage: 220V AC, Aux. contact: 1NO+1NC, Type: SDE-18	HPL	SDE1811A4	3	3
9	12.0-18A Thermal Overload Relay, Aux. Contact: 1NO + 1NC, Contactor Type: SDE Contactor, Type: SDER25	HPL	SDER25/18.0	1	1
10	Star Delta Timer, Time Setting: 3sec - 120sec, Voltage: 240V AC - 415V AC, Contact: 1CO (Star) + 1CO (Delta)	GIC	14SDT1S	1	1
11	SPP + Selectable Under Voltage+Selectable Over Voltage Relay ON Delay 0 - 15Sec,Phase 10% fixed Asymmetry, Voltage: 240 VAC,2 C/O, 3Ph/1Ph 4W, Type: SM500	GIC	MG73BH	1	1
12	1NO Contact Block	ESBEE	EC1C	1	1
13	1NC Contact Block	ESBEE	EC2C	1	1

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel. : +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



14	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
15	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	1
16	Amber Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLA240A	1	1
17	6A 1P 2Way Local - Remote/ Auto-Manual Switch with Center OFF, 60 Deg. Operation	SALZER	61025SAB13	1	1
G	OUTGOING MCCB 125A FOR AHU PANEL	MAKE	1	FEEDER QTY	1
1	125A 4P 25kA MCCB (with Spreaders), TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160CY125AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 125-160A TAB1 MCCB	HPL	TAB1160ST4P	1	1
3	ROHM compact Door mounted for TAB1 MCCB	HPL	RHCT1ACPDPM	1	1
4	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
5	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	1
6	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	1	1
7	Auxiliary Switch, Contacts: 1 C/O for TAB1 MCCB	HPL	TAB160AX1C	1	1
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 2.00MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 50X50X6MM & 450MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x50x5, N: 1X50X5 Material: Electrolytic grade COPPER Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Copper	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB
2	SR NO 50 AHU PANEL		BOARD QTY		
A	INCOMING MCCB 125A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	125A 4P 16kA MCCB (with Spreaders), TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160DX125AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
3	ROHM compact Door mounted for TAB1 MCCB	HPL	RHCT1ACPDPM	1	1
4	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
5	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	1
6	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	1	1
7	Auxiliary Switch, Contacts: 1 C/O for TAB1 MCCB	HPL	TAB160AX1C	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Multifunction Meter (LED display), 3Ph, Parameters: V, A, F, PF, kW, kVA, Old energy, On hours, site selectable kWh/ kVAh, CL: 1, Aux Sup: 90-300V AC/DC, Size: 96X96	L&T	WL4400100000	1	1
2	Ammeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1310100000	1	1
3	Voltmeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1320100000	1	1
4	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
5	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
6	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
7	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	3	3

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



8	200/5A 5VA Acc. Cl: 1, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 34mm	NIPPEN	NA	3	3
9	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
10	2A 1P 10kA C-Curve Techno MCB	HPL	NTSPC2	3	3
	OUTGOING AHU FAN MOTOR 5HP	MAKE	1	FEEDER QTY	1
1	63A 3P 16kA MCCB, TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160DX063AC3P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
3	Voltmeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1320100000	1	1
4	Ammeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1310100000	1	1
5	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
6	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	1
7	AC3: 9A AC1: 20A 3P Power Contactor, Coil Voltage: 220V AC, Aux. contact: 1NO+1NC, Type: SDE-09	HPL	SDE0911A4	1	1
8	7.0-10A Thermal Overload Relay, Aux. Contact: 1NO + 1NC, Contactor Type: SDE Contactor, Type: SDER25	HPL	SDER25/10.0	1	1
9	Star Delta Timer, Time Setting: 3sec - 120sec, Voltage: 240V AC - 415V AC, Contact: 1CO (Star) + 1CO (Delta)	GIC	14SDT1S	1	1
10	SPP + Selectable Under Voltage+Selectable Over Voltage Relay ON Delay 0 - 15Sec,Phase 10% fixed Asymmetry, Voltage: 240 VAC,2 C/O, 3Ph/1Ph 4W, Type: SM500	GIC	MG73BH	1	1
11	1NO Contact Block	ESBEE	EC1C	1	1
12	1NC Contact Block	ESBEE	EC2C	1	1
13	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
14	Green Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLG240A	1	1
15	Amber Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLA240A	1	1
16	6A 1P 2Way Local - Remote/ Auto-Manual Switch with Center OFF, 60 Deg. Operation	SALZER	61025SAB13	1	1
D	OUTGOING HEATER BANK	MAKE	1	FEEDER QTY	1
1	63A 3P 16kA MCCB, TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160DX063AC3P	1	1
2	Spreader Terminals (3 Pole - Set of 6 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST3P	1	1
3	20A 1PN 10kA C-Curve Techno MCB	HPL	NTSPNC20	6	6
	HUMIDIFIER	MAKE	1	FEEDER QTY	1
1	32A 4P 16kA MCCB, TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160DX032AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 20-100A TAB1 MCCB	HPL	TAB1100ST4P	1	1
F	WINTER HEATING CONTROLLING SYSTEM	MAKE	1	FEEDER QTY	1
1	CONTROLLING AND INTERLOCKING	REPUTED		1	1
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 2.00MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 50X50X6MM & 450MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x20x5, N: 1X20X5, Material: Electrolytic grade COPPER Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Copper	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21,Industrial Growth
Centre,Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



3	SR NO 51		BOARD QTY		
A	INCOMING MCCB 400A		1	FEEDER QTY	1
SR. NO.	BOQDESCRIPTION	MAKE	CATALOG NUMBER	QTY	TOTAL QTY
1	400A 4P 36kA MCCB (with Spreaders), TM Release (Adj Thermal & Adj Magnetic), Type : TAB3	HPL	TAB630NX400AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 400A TAB3 MCCB	HPL	TAB3400ST4P	1	1
B	METERING	MAKE	1	FEEDER QTY	1
1	Ammeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1310100000	1	1
2	Voltmeter with Inbuilt selector switch, 3Ph, Acc. CL: 1, Aux Supply: 80-300V AC, Size: 96X96	L&T	WL1320100000	1	1
3	Red Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLR240A	1	1
4	Yellow Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLY240A	1	1
5	Blue Gen Next Pro LED Indicator 22.5 mm, Voltage: 240V AC	ESBEE	EPLB240A	1	1
6	32A Neutral Link, Color: Black/Khaki	FTC	FNL 32	3	3
7	400/5A 10VA Acc. Cl: 1, ABS Insulated Bar Primary Ring Type Current Transformer, ID: 60mm	NIPPEN	NA	3	3
8	6 Sq.mm Disconnecting Terminal (Std. Color),Type: KUTSD 6	ELMEX	KUTSD 6	3	3
9	6A 1P 10kA C-Curve Techno MCB	HPL	NTSPC06	3	3
C	OUTGOING MCCB 315A	MAKE	1	FEEDER QTY	1
1	315A 4P 36kA MCCB (with Spreaders), TM Release (Adj Thermal & Adj Magnetic), Type : TAB3	HPL	TAB630NX315AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 315A TAB3 MCCB	HPL	TAB3315ST4P	1	1
D	OUTGOING MCCB 160A	MAKE	1	FEEDER QTY	1
1	160A 4P 25kA MCCB (with Spreaders), TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160CY160AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 125-160A TAB1 MCCB	HPL	TAB1160ST4P	1	1
E	OUTGOING MCCB 125A	MAKE	1	FEEDER QTY	1
1	125A 4P 25kA MCCB (with Spreaders), TA Release (Adj Thermal & Fixed Magnetic), Type : TAB1	HPL	TAB160CY125AC4P	1	1
2	Spreader Terminals (4 Pole - Set of 8 Nos.) for 125-160A TAB1 MCCB	HPL	TAB1160ST4P	1	1
S.N.	FABRICATION DETAILS	MAKE	TYPE/MATERIAL	QTY	UNIT
1	FABRICATION : 2.00MM CRCA Sheet PRE TREATMENT: 7 TANK PROCESS PAINTING: POWDER COATED WITH SIEMENS GREY SHED (RAL 7032) TYPE: INDOOR TYPE, FREE FLOOR RESTING, FIX TYPE, SINGLE FRONT, COMPARTMENTLISED DESIGN, SINGLE DOOR CABLE ENTRY: TOP/BOTTOM (DETACHABLE GLAND PLATE UNDRILLED)	DVEPL	MS/CRCA	1	JOB
2	BASE FRAME: 35X35X6MM & 500MM	DVEPL	ISMC	1	JOB
3	BUSBAR: PH: 1x60x10, N: 1X60X10 Material: Electrolytic grade Aluminum Current Density: 1 Amp/Sq. mm Insulation: Color coded heat shrinkable Sleeves	DVEPL	Aluminum	1	JOB
4	WIRING HARNESS (METERING STARTERS)	DVEPL	CU- WIRE	1	LOT
5	HARDWARE & ACCESSORIES (LOCKS, GASKET, NUT BOLT ETC)	DVEPL	NUT, BOLTS, LUGS ETC.	1	LOT
6	LABOUR	DVEPL		1	JOB

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax : +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M : +91 94170 21685, +91 94176 01244
E : dvepl@yahoo.in, office@dvepl.com
W : www.dvepl.com



ANNEXURE – III

PRICE SCHEDULE

SR. NO.	DESCRIPTION OF ITEM	QTY	UNIT RATE (INR)	AMOUNT (INR)
1	SR NO 49	1	1,90,100.00	1,90,100.00
2	SR NO 50 AHU PANEL	1	69,600.00	69,600.00
3	SR NO 51	1	74,500.00	74,500.00
TOTAL QUANTITY		3	TOTAL COST (INR)	3,34,200.00

In words: Rupees Three Lac Thirty Four Thousand Two Hundred Only

NOTES:

MANUFACTURERS OF LT CONTROL PANELS

Regd. - Administrative Office :
Prabhu Niwas Building, Near Ranbir (Kalu) Petrol Pump,
Dalhousie Road, Pathankot - 145001.
Tel-Fax | +91 186 2231231

Factory :
F03, F04, F21, Industrial Growth
Centre, Pathankot - 145001
Tel.: +91 92572 17609

Sales Office
202 2nd Floor, Golden Square Building,
Chandigarh, Amabala Highway Zirakpur.

M | +91 94170 21685, +91 94176 01244
E | dvepl@yahoo.in, office@dvepl.com
W | www.dvepl.com



ANNEXURE – IV

COMMERCIAL TERMS AND CONDITIONS

PRICE:	Ex works – IGC PATHANKOT (PB.)
PACKING & FORWARDING:	Extra as per actual
FREIGHT & INSURANCE:	Extra Freight & insurance.
GST:	18% or Actual As per Gst Taxation.
OCTROI:	Extra as applicable.
PAYMENT TERMS:	50% in advance with confirmed order and balance against Performa invoice before dispatch.
ORDER PLACEMENT:	D.V. ELECTROMATIC PVT.LTD
DELIVERY:	6-8 Weeks from the date of approval of drawings.
VALIDITY	Our offer is valid for 15 Days from the date of this offer and thereafter subject to our confirmation.
WARRANTY:	18 Months from the date of supply or 12 months from the commissioning whichever ends earlier.
INSPECTION:	On intimation, prior inspection of the panels, if required, may be carried out by the buyers authorized representative at our works at IGC - Pathankot (pb.)
ORDER AMENDMENTS:	Any change in specifications & other terms shall entail revision of delivery and prices including statutory variations.
FORCE MAJEURE:	We shall not be responsible for the failure or delay in order due to acts beyond our control such as war, fire, labour problems, accidents, natural calamities, government acts or shortage of material.
COMMISSIONING CHARGES	2500/Men days Testing, Commissioning and programming with Logging, fooding and boarding in Customer scope. Unloading, Fixing, Laying cables and Installation of panels at site are not in our scope.

Our Bank Details:

HDFC Bank
DALHOUSIE ROAD, PATHANKOT-145001
A/c # 50200012824476
IFSC Code: HDFC0002459

MANUFACTURERS OF LT CONTROL PANELS